

Section II: Scope of Work

1. Replacement of Exterior Doors, interior bathroom doors.

- a. Replace the threshold with heavy duty aluminum unit. Replace the 3'x7' metal door with insulated metal door with vision panel. The new door should be pre-finished with rust inhibiting treatment. Finish existing frame with rust inhibiting primer and two coats of low VOC rust inhibiting paint. Provide door closer and panic hardware.
- b. Replace the two metal doors with 20 minute rated 3'x7' solid core wood doors with vision panels and 6"x32" stainless steel kick plates on the inside. Provide closers and latching hardware so doors self-close and self-latch.
- c. Replace existing double doors (3'-0" x 7'-0" each) with heavy duty insulated steel doors with two view panels per door. Provide new closers, self-latching mechanisms, sweeps, continuous neoprene gaskets, and panic devices. Paint doors to match existing frame. Also add a heavy duty removable mullion to the frame. These doors should be similar to the new doors at the dining hall. And, painted with rust inhibiting primer and two coats of low VOC rust inhibiting paint.

2. Replacement of Plexiglas windows.

- a. Replace approximately 114 SF Plexiglas glazing with insulated safety glazing in 8 existing frames. The new glazing should have an R value of at least 3.

Proposals must include installation of the all equipment to code and meet all safety standards. Proposals must also include Davis-Bacon wages listed separately in the quote. Installation needs to be completed by 6/30/16. Vendors need to quote each project individually. Contractor is responsible for all work and must field verify all measurements.

Point of Contact:

David Whittinghill, Maintenance Manager
Muhlenberg Job Corps center
(270) 377-3304
3875 State Route 181 N
Greenville, KY 42345

Alternate Point of Contact:

Trevor Periard, F&A Director
Muhlenberg Job Corps Center.
(270) 377-3255